

Detailed Estimate

SoR Period: 10/04/2025 - 31/03/2026 Created By: BRIJBHUSHAN PANDEY

GP LAGHUWAI ME NAHAR KE KINARE BRIKHSAROPAN KARY

3156002039/DP/VB/YD/958486255824341453

BLOCK: FATEHPUR MADAUN, GRAMA PANCHAYAT : LAGHUWAI

Heading / Description: 1 - EARTH WORK								
1	77.3.5.3 -- साधारण मिट्टी में खुदाई का कार्य - वृक्षारोपण गड्ढे: 0.45x0.45x0.45 मी० साईज के गड्ढे							
SI No	Description	No	L	B	D	CF	Quantity	Remark
77.3.5.3								
1	FOR 1000 PLANT	1000	0.450	0.450	0.450	1.0	91.1250	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	0.6024	300.0	180.72	54.8946	16468.37	
Total Quantity						91.1250 cum		
Total Deducted Quantity						0.0000 cum		
Net Total Quantity						91.13 cum		
Say 91.1250 cum @ (₹) 182.53012 / cum						16633.06		
Unskilled wage						16468.37		
Unskilled Person-days						54.89457844500001		
2	77.9.2 -- वृक्षारोपण कार्य : गड्ढों का रेखांकन, ट्रेंच एवं सी0 पी0 टी0							
SI No	Description	No	L	B	D	CF	Quantity	Remark
77.9.2								
1	FOR 1000 PLANT	1000				1.0	1000.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	0.0020	300.0	0.6	2.0000	600.0	
Total Quantity						1000.0000 Plant		
Total Deducted Quantity						0.0000 Plant		
Net Total Quantity						1000.00 Plant		
Say 1000.0000 Plant @ (₹) 0.606 / Plant						606.00		
Unskilled wage						600.00		
Unskilled Person-days						2.0		
3	77.9.3 -- वृक्षारोपण कार्य : कार्य स्थल तक ढुलाई							
SI No	Description	No	L	B	D	CF	Quantity	Remark

77.9.3								
1	FOR 1000 PLANT	1000				1.0	1000.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	0.0020	300.0	0.6	2.0000	600.0	
Total Quantity					1000.0000 Plant			
Total Deducted Quantity					0.0000 Plant			
Net Total Quantity					1000.00 Plant			
Say 1000.0000 Plant @ (₹) 0.606 / Plant					606.00			
Unskilled wage					600.00			
Unskilled Person-days					2.0			
4	77.9.4 -- वृक्षारोपण कार्य: छोटे पौधों को कार्यस्थल से रोपण स्थल तक पहुंचाने की दुलाई							
SI No	Description	No	L	B	D	CF	Quantity	Remark
77.9.4								
1	FOR 1000 PLANT	1000				1.0	1000.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	0.0020	300.0	0.6	2.0000	600.0	
Total Quantity					1000.0000 Plant			
Total Deducted Quantity					0.0000 Plant			
Net Total Quantity					1000.00 Plant			
Say 1000.0000 Plant @ (₹) 0.606 / Plant					606.00			
Unskilled wage					600.00			
Unskilled Person-days					2.0			
5	77.9.6.2 -- वृक्षारोपण कार्य: गड्डों में पौधे लगाने व रीफिलिंग : 0.45x0.45x0.45 मी०							
SI No	Description	No	L	B	D	CF	Quantity	Remark
77.9.6.2								
1	FOR 1000 PLANT	1000				1.0	1000.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	0.0149	300.0	4.48	14.9254	4477.61	
Total Quantity					1000.0000 Plant			
Total Deducted Quantity					0.0000 Plant			
Net Total Quantity					1000.00 Plant			
Say 1000.0000 Plant @ (₹) 4.522388 / Plant					4522.39			
Unskilled wage					4477.61			
Unskilled Person-days					14.925373333333333			
6	77.12.1 -- प्रत्येक पौधे की देखरेख, मिट्टी कार्य एवं बाड़ों की मरम्मत (ग्राम सभाकी अनु० जाति / जनजाति, बीपीएल पट्टेदार की भूमि पर लगाये गये पौधरोपण सहित)							

SI No	Description	No	L	B	D	CF	Quantity	Remark
77.12.1								
1	01 BELDAR FOR 90 DAYS AFTER PLANTATION	90				1.0	90.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	1.0000	300.0	300.0	90.0000	27000.0	
Total Quantity					90.0000 Day			
Total Deducted Quantity					0.0000 Day			
Net Total Quantity					90.00 Day			
Say 90.0000 Day @ (₹) 300.0 / Day					27000.00			
Unskilled wage					27000.00			
Unskilled Person-days					90.0			
7	77.16 -- पौधों की हैंडपंप/ बोरबेल/ ओपेनवेल से सिंचाई 30 मी0 से अधिक दूरी तक							
SI No	Description	No	L	B	D	CF	Quantity	Remark
77.16								
1	EACH PLANTS 6 TIMES	1000				6.0	6000.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	0.0071	300.0	2.14	42.8571	12857.14	
Total Quantity					6000.0000 Plant			
Total Deducted Quantity					0.0000 Plant			
Net Total Quantity					6000.00 Plant			
Say 6000.0000 Plant @ (₹) 2.164286 / Plant					12985.72			
Unskilled wage					12857.14			
Unskilled Person-days					42.857139999999994			
8	77.50.11 -- गोबर की खाद (2 किलो प्रति गड्ढा) की आपूर्ति							
SI No	Description	No	L	B	D	CF	Quantity	Remark
77.50.11								
1	FOR 1000 PLANT	1000				1.0	1000.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
MR2226	गोबर की खाद (2 किलो प्रति गड्ढा)	each	1.0000	10.0	10.0	1000.0000	10000.0	
Total Quantity					1000.0000 each			
Total Deducted Quantity					0.0000 each			
Net Total Quantity					1000.00 each			
Say 1000.0000 each @ (₹) 10.0 / each					10000.00			
9	77.50.12 -- गड्ढा भरने हेतु कीटनाशक (प्रति गड्ढा) की आपूर्ति							
SI No	Description	No	L	B	D	CF	Quantity	Remark

77.50.12								
1	FOR 1000 PLANT	1000				1.0	1000.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
MR2227	गड्ढा भरने हेतु कीटनाशक	each	1.0000	0.41	0.41	1000.0000	410.0	
Total Quantity						1000.0000 each		
Total Deducted Quantity						0.0000 each		
Net Total Quantity						1000.00 each		
Say 1000.0000 each @ (₹) 0.41 / each						410.00		
10	77.50.15 -- रासायनिक उर्वरक (25 ग्राम प्रति पौधा) की आपूर्ति							
SI No	Description	No	L	B	D	CF	Quantity	Remark
77.50.15								
1	FOR 1000 PLANT	1000				1.0	1000.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
MR2230	रासायनिक उर्वरक 25 ग्राम प्रति पौधा	each	1.0000	0.65	0.65	1000.0000	650.0	
Total Quantity						1000.0000 each		
Total Deducted Quantity						0.0000 each		
Net Total Quantity						1000.00 each		
Say 1000.0000 each @ (₹) 0.65 / each						650.00		
Heading / Description: 2 - PLANTATION								
1	77.7.5 -- सामग्री चढ़ाई एवं उत्तराई : पौधे							
SI No	Description	No	L	B	D	CF	Quantity	Remark
77.7.5								
1	FOR 1000 PLANT	1000				1.0	1000.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	0.0020	300.0	0.6	2.0000	600.0	
Total Quantity						1000.0000 no		
Total Deducted Quantity						0.0000 no		
Net Total Quantity						1000.00 no		
Say 1000.0000 no @ (₹) 0.606 / no						606.00		
Unskilled wage						600.00		
Unskilled Person-days						2.0		
2	77.50.4 -- दो वर्षीय पौधे (पिंडी) की आपूर्ति							
SI No	Description	No	L	B	D	CF	Quantity	Remark
77.50.4								
1	FOR 1000 PLANT	1000				1.0	1000.0000	-

LIST							
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)
MR2219	दो वर्षीय पौधे पिंडी	each	1.0000	23.0	23.0	1000.0000	23000.0
Total Quantity					1000.0000 each		
Total Deducted Quantity					0.0000 each		
Net Total Quantity					1000.00 each		
Say 1000.0000 each @ (₹) 23.0 / each					23000.00		
3	Lump sum Type : Admin	Worksite facilities/Creche/Drinking water/First aid					1000.0
4	Lump sum Type : Material	Display Board / CIB					5250.0
5	Lump sum Type : Material	Miscellaneous /Contingencies charges					531.0
Shape Type							LINE
Measurement						Length (in Meter)	200
Total (₹) :							104406.16
Rounded Total (₹) :							1,04,406.00
Rupees One Lakh Four Thousand Four Hundred and Six Only							
Unskilled Manpower wages							63203.13
Materials (Includes Extra Charges)							34422.03
Carriage							0.00
Skilled							0.00
SemiSkilled							0.00
Lumpsum Admin							1000.00
Lumpsum Material							5781.00
No of Person days							210.68

Site Before





Latitude: 26.111962
Longitude: 83.754485
Elevation: 77.28±11.8 m
Accuracy: 3.0 m
Time: 27-07-2026 12:32

Note: ग्राम पंचायत लधुवाई में नहर के किनारे वृक्षारोपण कार्य

Powered by NoteCam