

Detailed Estimate

SoR Period: 10/04/2025 - 31/03/2026 Created By: BRIJBHUSHAN PANDEY

GP DHARMPUR BISHUNPUR ME LILHAWA PICH MARG SE KAILASH KE GHAR TAK CHAK MARG KARY

3156002018/RC/VB/YD/958486255824280943

BLOCK: FATEHPUR MADAUN, GRAMA PANCHAYAT : DHARAMPUR BISHUNPUR

Heading / Description: 1 - Item of work								
1	77.TM.A.19.1.AF -- Earthwork in filing for construction of road embankment from borrow pits with a lead up to 10 m and lift up to 1.5 m, spreading, grading, laying in 20 cm layers to required slope and camber, compacting with hand rammer complete as directed (rolling with road roller to be done where ever required). Ordinary Soil. (Work executed by Abled Female)							
SI No	Description	No	L	B	D	CF	Quantity	Remark
Earthwork in filing.								
1	00.00 to 150.00 m	3	50.000	(3.00+4.80)/2	0.900	1.0	526.5000	-
Existing in earth work quantity.								
2	00.00 to 50.00 m	1	50.000	2.650	0.340	1.0	-45.0500	-
3	50.00 to 100.00 m	1	50.000	2.530	0.320	1.0	-40.4800	-
4	100.00 to 150.00 m	1	50.000	2.670	0.350	1.0	-46.7250	-
Deductions.								
5	Deduct 12.5 percent S.A.	1	394.245			0.13	-49.2810	-
6	Deduct 50 percent of earth work for abled male.	1	344.964			0.5	-172.4820	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	1.0989	300.0	329.67	189.5407	56862.2	
Total Quantity					526.5000 cum			
Total Deducted Quantity					-354.0180 cum			
Net Total Quantity					172.48 cum			
Say 172.4820 cum @ (₹) 329.67033 / cum					56862.20			
Unskilled wage					56862.20			
Unskilled Person-days					189.54065953019992			
2	77.TM.A.19.1.AM -- Earthwork in filing for construction of road embankment from borrow pits with a lead up to 10 m and lift up to 1.5 m, spreading, grading, laying in 20 cm layers to required slope and camber, compacting with hand rammer complete as directed (rolling with road roller to be done where ever required). Ordinary Soil. (Work executed by Abled Male)							
SI No	Description	No	L	B	D	CF	Quantity	Remark
Work executed by abled male.								
1	50 percent of earth work.	1	344.964			0.5	172.4820	-
LIST								

Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	0.9709	300.0	291.26	167.4583	50237.48	
Total Quantity					172.4820 cum			
Total Deducted Quantity					0.0000 cum			
Net Total Quantity					172.48 cum			
Say 172.4820 cum @ (₹) 291.262136 / cum					50237.48			
Unskilled wage					50237.48			
Unskilled Person-days					167.45825247184			
3	77.55.1 -- Taking services of Beldar for drinking water arrangement							
SI No	Description	No	L	B	D	CF	Quantity	Remark
1	Beldar.	1	14.000			1.0	14.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0114	Beldar	Day	1.0000	300.0	300.0	14.0000	4200.0	
Total Quantity					14.0000 Day			
Total Deducted Quantity					0.0000 Day			
Net Total Quantity					14.00 Day			
Say 14.0000 Day @ (₹) 300.0 / Day					4200.00			
Unskilled wage					4200.00			
Unskilled Person-days					14.0			
4	77.55.7 -- Employing Mate for supervision of labour engaged on work.							
SI No	Description	No	L	B	D	CF	Quantity	Remark
1	Mate.	1	14.000			1.0	14.0000	-
LIST								
Code	Description	Unit	Quantity	Rate(₹)	Amount (₹)	Total Quantity	Total Amount (₹)	
0128	Mate	Day	1.0000	310.0	310.0	14.0000	4340.0	
Total Quantity					14.0000 Day			
Total Deducted Quantity					0.0000 Day			
Net Total Quantity					14.00 Day			
Say 14.0000 Day @ (₹) 310.0 / Day					4340.00			
2	Lump sum Type : Material	Display Board / CIB						5250.0
3	Lump sum Type : Material	Miscellaneous /Contingencies charges						531.0
Shape Type								LINE
Measurement							Length (in Meter)	150
Total (₹) :								121420.67
Rounded Total (₹) :								1,21,421.00

Rupees One Lakh Twenty One Thousand Four Hundred and Twenty One Only	
Unskilled Manpower wages	111299.67
Materials (Includes Extra Charges)	0.00
Carriage	0.00
Skilled	0.00
SemiSkilled	4340.00
Lumpsum Admin	0.00
Lumpsum Material	5781.00
No of Person days	371.00

Site Before

